



Link Name	1.000	1.001	1.002	1.003	1.004
Section Type	225mm	225mm	225mm	225mm	225mm
Slope (1:X)	1:60.0	1:60.0	1:130.0	1:130.0	1:130.0
Cover Level (m)	66.800	66.600	66.200	66.900	66.500
Invert Level (m)	64.800	64.504 64.504	64.052 64.052	63.442 63.442	63.381 63.381
Length (m)	17.789	27.110	44.218	35.161	7.917



Link Name	2.000
Section Type	225mm
Slope (1:X)	1:60.0
Cover Level (m)	66.200
Invert Level (m)	64.357
Length (m)	35.568



Link Name	3.000	3.001
Section Type	225mm	225mm
Slope (1:X)	1:70.0	1:70.0
Cover Level (m)	67.500	67.000
Invert Level (m)	63.635 63.539	63.539 63.360
Length (m)	6.692	12.531

- GENERAL NOTES**
- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEER'S AND ARCHITECT'S DRAWINGS AND SPECIFICATIONS.
 - ALL LEVELS ARE IN METRES TO ORDNANCE DATUM, MALIN HEAD UNLESS NOTED OTHERWISE.
 - THE POSITION OF EXISTING SERVICES AS SHOWN ON THE DRAWING MAY NOT BE ACCURATE. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR LOCATING ALL EXISTING SERVICES ON THE SITE AND SHOULD CONTACT THE RESPECTIVE UTILITY PROVIDERS AND AUTHORITIES FOR THE MOST UP-TO-DATE INFORMATION BEFORE COMMENCING THE WORKS.
 - EXISTING LEVELS ARE INDICATIVE ONLY AND MUST BE CHECKED AND VERIFIED ON SITE PRIOR TO COMMENCEMENT.
 - PROPOSED MANHOLE COVER LEVELS ARE APPROXIMATE AND SHOULD BE ADJUSTED TO SUIT LOCAL FINISHES.
 - ALL SURFACE WATER DRAINAGE INFRASTRUCTURE SHALL BE CONSTRUCTED IN ACCORDANCE WITH LOCAL AUTHORITY REQUIREMENTS.
 - LOCKABLE TYPE GULLY TRAPS TO BE USED ON ALL SURFACE WATER DRAINS.
 - GULLY POSITIONS ARE APPROXIMATE ONLY AND SHOULD BE LOCATED AT LOW POINTS.
 - REFER TO ARCHITECTS' DRAWINGS FOR ALL ROOF DRAINAGE, STRIP DRAINS AND GULLY TRAPS BENEATH DOWNPIPES.
 - WHERE IT IS NOT POSSIBLE TO ACHIEVE MINIMUM COVER, PIPES SHOULD BE BEDDED AND SURROUNDED IN CONCRETE 150MM THICK, CLASS E IN ACCORDANCE WITH T11 STANDARD CONSTRUCTION DETAIL CC-SCD-00521.
 - ALL WASTEWATER DRAINAGE INFRASTRUCTURE SHALL BE CONSTRUCTED IN ACCORDANCE WITH IRISH WATER STANDARDS. REFER TO IRISH WATER PUBLICATIONS "WASTEWATER INFRASTRUCTURE STANDARD DETAILS - IW-CDS-5030-01" AND "CODE OF PRACTICE FOR WASTEWATER INFRASTRUCTURE - IW-CDS-5030-03".
 - HYDRANTS TO BE ACCORDANCE WITH IRISH WATER STANDARD DETAILS STD-W-16 TO STD-W-19.
 - THRUST BLOCK ARRANGEMENTS SHALL COMPLY WITH IRISH WATER STANDARD DETAILS STD-W-28.
 - REFER TO MECHANICAL AND ELECTRICAL ENGINEER'S DRAWINGS FOR INTERNAL DRAINAGE AND DETAILS OF SOIL AND VENT PIPES LEADING TO WASTEWATER DRAINAGE AJS.
 - ALL WATER INFRASTRUCTURE SHALL BE CONSTRUCTED IN ACCORDANCE WITH IRISH WATER STANDARDS. REFER TO IRISH WATER PUBLICATIONS "WATER INFRASTRUCTURE STANDARD DETAILS - IW-CDS-5020-01" AND "CODE OF PRACTICE FOR WATER INFRASTRUCTURE - IW-CDS-5020-03".
 - ALL PLANTING & TREES TO COMPLY WITH SEPERATION DISTANCES AS PER IRISH WATER STANDARD DETAILS FOR WASTEWATER, STD-WW-06 AND STD-WW-06A AND FOR WATER, STD-W-12 AND STD-W-12A.
 - A METHOD STATEMENT SHALL BE SUBMITTED FOR APPROVAL PRIOR TO INSTALLATION AND TESTING.
 - ALL PIPE DIAMETERS INDICATED ARE INNER DIAMETER.
 - THESE DRAWINGS ARE NOT TO BE USED FOR SETTING OUT PURPOSES. REFER TO ARCHITECTS DRAWINGS FOR SETTING OUT.

INFORMATION

© ORS
This drawing and any design hereon is the copyright of the Consultants and must not be reproduced without their written consent. All drawings remain the property of the Consultants.

Figured dimension only to be taken from this drawing. All dimensions to be checked on site. Consultants to be informed immediately of any discrepancies before work proceeds.

REV NO:	DATE:	REVISION NOTE:	DWN BY:	CKD BY:
P01	23/01/2024	ISSUED FOR PLANNING	PMC	MH

CLIENT:	WESTMEATH COUNTY COUNCIL		
PROJECT:	PROPOSED SERVICED SITES KILLENBOYLEGAN, MOATE, CO. WESTMEATH		
TITLE:	FOUL SEWER LONGITUDINAL SECTIONS		
DRAWN: PMC	CHECKED: RD	APPROVED: MH	JOB NO: 230894
DATE: OCT. 2023	SCALE: 1:500	DRAWING NO: 230894-ORS-Z2-ZZ-DR-CE-410	REV: P01

